BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Construction of Building and Development of Govt. School and improvements in school Premises at Jakkuralli village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
1	Dismantling of existing structures like culverts. bridges. retaining walls and other structure comprising of masonry. cement concrete. wood work. steel work. including T&P and scaffolding wherever necessary. sorting the dismantled material. disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications.	Cum	93.46	202.00	Rupees Two Hundred Two Only
2	Dismantling of existing structures like culverts. bridges. retaining walls and other structure comprising of masonry. cement concrete. wood work. steel work. including T&P and scaffolding wherever necessary. sorting the dismantled material. disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. ii) Dismantling Brick / Tile work. A. In lime mortar.	Cum	219.04	200.00	Rupees Two Hundred Only
3	Dismantling of existing structures like culverts. bridges. retaining walls and other structure comprising of masonry. cement concrete. wood work. steel work. including T&P and scaffolding wherever necessary. sorting the dismantled material. disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. Prestressed Reinforced cement concrete grade M-20 & above.	Cum	122.45	900.00	Rupees Nine Hundred Only
4	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms).	Sqm	562.28	51.00	Rupees Fifty One Only
5	Dismantling of existing structures like culverts. bridges. retaining walls and other structure comprising of masonry. cement concrete. wood work. steel work. including T&P and scaffolding wherever necessary. sorting the dismantled material. disposal of unserviceable material and stacking the serviceable material with all lifts complete as specification Rubble stone masonry in cement mortar.	Cum	152.15	200.00	Rupees Two Hundred Only
6	Conveying the excavated debries and over burden earth etc to a lead 20 kms distances by using private vehicles this including the cost of loading and inloading charges etc	Cum	836.33	150.00	Rupees One Hundred Fifty Only
7	Earth work in excavation of foundation of structures as per drawingand technical specification. including setting out. construction of shoring and bracing. removal of stumps and other deleterious matter. dressing of sides and bottom. backfilling the excavation earth to the extent required and utilising the remaining earth locally for the work-in.Ordinary/Hard soil-Mechanical Means (Depth upto 3 m)	Cum	346.73	100.0	Rupees One Hundred Only
8	Earthwork excavation for foundation of buildings. culverts. water supply. sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width. in ordinary soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches. stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.	Cum	111.31	200.0	Rupees Two Hundred Only
9	Filling available excavated earth (excluding rock) insides of foundations upto plinth in layers not exceeding 20cms. In depth. compacting each deposited layer by ramming after watering with a lead upto 50m. And lift upto 1.5m including cost of all labour (Inside platrform . sides and sides of the area)	Cum	229.02	150.0	Rupees One Hundred Fifty Only

For K. DAMODAR & CO.

For K. DAMODAR & CO

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Construction of Building and Development of Govt. School and improvements in school Premises at Jalahalli village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
10	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs. with 40mm and down size graded granite metal coarse aggregate @ 0.892cum and fine aggregates @ 0.465cum machine mixed. machinemixed. concrete laid in layers not exceeding 15 cms. thick well compacted in foundation and plinth. cost of all materials. labour HOM of machinery. curing complete as per specifications.	Cum	134.35	6000.00	Rupees Six Thousand Only
11	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs. with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum. with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008. machine mixed. concrete laid in layers not exceeding 15 cms thick. vibrated for all works in foundation plinth and ground floor level for roof slabs. staircase. lintles. retaining walls. return walls. walls (any thickness) including attached plasters. columns. piers. abutments. pillars. posts. struts. buttresses. string or lacing courses. parapets. coping. bed blocks. anchor blocks.& Plinths etc.. including cost of all materials. labour. HOM of machinery. curing. complete as per specifications Footing	Cum	78.84	7300.00	Rupees Seven Thousand Three Hundred Only
12	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs. with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum. with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008. machine mixed. concrete laid in layers not exceeding 15 cms thick. vibrated for all works in foundation plinth and ground floor level for roof slabs. staircase. lintles. retaining walls. return walls. walls (any thickness) including attached plasters. columns. piers. abutments. pillars. posts. struts. buttresses. string or lacing courses. parapets. coping. bed blocks. anchor blocks.& Plinths etc.. including cost of all materials. labour. HOM of machinery. curing. complete as per specifications Columns	Cum	19.74	7300.00	Rupees Seven Thousand Three Hundred Only
13	Providing & removing centering shuttering. strutting. propping etc.. and removal of form work for foundations. footings bases of columns for mass concrete including cost of all materials. labour complete as per specifications Footing	Sqm	196.56	300.0	Rupees Three Hundred Only
14	Providing and removing Centering. shuttering. strutting. propping etc.. for columns. pillars. piers. abutments. post and struts. square / rectangular / polygon in plan including cost of materials. labour complete as per specification and directions of the Engineer in charge.	Sqm	279.54	500.0	Rupees Five Hundred Only
15	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregares of ready mixef concrete for RCC works laid in 15 cms thick layers and well compated including vibrating. curing.etc.. with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams. Staircase and Roof with M-25 Plinth Beam	Cum	40.75	7300.00	Rupees Seven Thousand Three Hundred Only
16.	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregares of ready mixef concrete for RCC works laid in 15 cms thick layers and well compated including vibrating. curing.etc.. with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams. Staircase and Roof with M-25 Roof Slab	Cum	133.17	7300.00	Rupees Seven Thousand Three Hundred Only

For K. DAMODAR & CO.

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK:Construction of Building and Development of Govt. School and improvements in school Premises at Jakkasandra village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
17	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregares of ready mixef concrete for RCC works laid in 15 cms thick layers and well compated including vibrating. curing.etc., with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams. Staircase and Roof with M-25 Roof Beams	Cum	27.17	7300.00	Rupees Seven Thousand Three Hundred Only
18	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregares of ready mixef concrete for RCC works laid in 15 cms thick layers and well compated including vibrating. curing.etc., with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams. Staircase and Roof with M-25 Staircase. Basement floor to G floor	Cum	4.64	7300.00	Rupees Seven Thousand Three Hundred Only
19	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6. edges of stones chistle dressed in courses not less than 15 cms high. bond stones at two m. apart in each course including cost of materials. labour. curing complete as per specification.	Cum	81.85	6000.0	Rupees Six Thousand Only
20	Providing and removing Centering. shuttering. strutting. propping etc..and removal of from work for vertical surface such as walls at any thickness including attched plasters. butresses. plinth cills and string courses cost of all materials. labour complete as per specification	Sqm	407.48	375.0	Rupees Three Hundred Seventy Five Only
21	Providing and removing cenering. shuttering. strutting. propping etc.. and removal of form work for flat surface such as suspended floors. roofs. landings. balconies and likes. thickness upto 200 mm including cost of all materials. labour complete as per specifications	Sqm	853.71	600.0	Rupees Six Hundred Only
22	Providing and removing centering. shuttering. strutting. propping etc.. and removal of form work for sides and soffits of beams. beam haunchings. cantilever girders. bressumers and lintles exceeding 1 m in depth incluidng cost of all materials. labour complete as per specifications.	Sqm	362.21	500.0	Rupees Five Hundred Only
23	Providing and removing centering. shuttering. strutting. propping etc.. and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials. labour complete as per specificaiton. Staircase.	Sqm	35.65	500.0	Rupees Five Hundred Only
24	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs. with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregetes @ 0.47cum. with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008. machine mixed. concrete laid in layers not exceeding 15 cms thick. vibrated for all works in foundation plinth and ground floor level for roof slabs. staircase. lintles. retaining walls. return walls. walls (any thickness) including attached plasters. columns. piers. abutments. pillars. posts. struts. buttresses. string or lacing courses. parapets. coping. bed blocks. anchor blocks. plain window cills. fillets etc.. including cost of all materials. labour. HOM of machinery. curing. complete as per specifications.	Cum	2.43	7300.00	Rupees Seven Thousand Three Hundred Only
25	Providing & removing centering shuttering.strutting. propping etc.. and removal of form work for sides & soffits of beams. beam haunchings. cantilever girders. bresumers and lintels not exceeding 1m in depth including cost of all materials. labour complete as per specifications.	Sqm	37.98	500.0	Rupees Five Hundred Only

For K. DAMODAR & CO.

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Construction of Building and Development of Govt. School and improvements in school Premises at Jalahalli village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
26	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs. with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum. with superplastisiser @0.225lts. machine mixed. well compacted for plain chajja of 7.5 cms. average thickness. upto ground floor level. including cost of all materials. labour. HOM of machinery. finishing. curing. complete as per specifications.	Sqm	14.16	650.0	Rupees Six Hundred Fifty Only
27	Providing and removing centering. shuttering. strutting. propping etc.. for chajjas. corbels etc.. including edges including cost of all materials. labour complete as per specificaiton.	Sqm	14.16	500.0	Rupees Five Hundred Only
28	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion. jamb. closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials. labour charges. scaffolding. curing complete as per specifications.	Sqm	723.70	1100.00	Rupees One Thousand One Hundred Only
29	Providing and constructing non-load bearing wall with cement concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 (Jamb. closer blocks) with blocks of size 40x10x20cms. (lxbxh) conforming to I.S : 2185/1965 in superstructure including cost of materials. labour charges. scaffolding. curing complete as per specifications.	Sqm	72.24	900.00	Rupees Nine Hundred Only
30	Providing 12mm thick cement plaster in single coat with cement mortar 1:4. to ceiling including rounding off corners wherever required smooth rendering.. Providing and removing scaffolding. including cost of materials. labour. lead. lift. curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials. labour. curing complete as per specification.	Sqm	853.71	300.0	Rupees Three Hundred Only
31	Providing 18mm thick cement plaster in single coat with cement mortar 1:4. to brick masonry including rounding off corners wherver required smooth rendering. : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding. cost of materials. labour. curing complete as per specifications. direction of the Engineer in charge.for Inside Plastering.	Sqm	1110.44	300.0	Rupees Three Hundred Only
32	Providing 18mm thick cement plaster in single coat with cement mortar 1:4. to brick masonry including rounding off corners wherver required smooth rendering. : Providing and removing scaffolding. cost of materials. labour. curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering.	Sqm	951.78	300.0	Rupees Three Hundred Only
33	Providing TMT Steel Reinforcement for R.C.C work including straightening. cutting. bending. hooking. placing in position. lapping and / or welding wherever required. tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials. labour. HOM of machinery complete as per specifications.TMT Bars Fe 500.	Tonne	25.30	75000.00	Rupees Seventy Five Thousand Only
34	Providing Sal wood frames of doors. windows. clerestory windows. ventilators and other frames. wrought. framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps). but including cost of materials. labour. HOM of machineries complete as per specifications.	Cum	1.48	110000.0	Rupees One Lakh Ten Thousand Only

For K. DAMODAR & CO.